



2929 Storey Ln
Dallas, TX 75220
Office 972-224-1669
Fax 214-352-1049

Date: 4/5/2022

City of Saginaw

Aquatic Center – Safety and Mechanical Repairs required as result of damage in February 2021

SCOPE OF WORK:

- Aquatic Center Renovations
- Safety and Mechanical Repairs
- Project based on 7 to 10 days for completion, weather permitting
- **PROJECT TOTAL: \$23,045.89**

Filter Media

- Remove filter media from 2 ea. Stark Filter
- Inspect integrity of laterals and piping
- Dispose of removed filter media and install new sand and gravel per manufacturer's specifications
- Laterals will be inspected and replaced as required and added to final invoice, not to exceed proposed contingency in quote.
- Upon completion refill filters and start filtration system
- Media replacement and lateral inspection was not covered in original renovation and seems laterals may have been damaged by freeze in February since customer is seeing what appears to be filter sand in the swimming pool
- **Media Replacement / Labor - \$6450.00**
- **Lateral/Gasket Contingency - \$2600.00**

Beach Entry Safety Grating

- Replace 110ft of 12" T-Bar Safety Grating on beach entry gutter.
- Includes 110 ft new grates, hardware, installation labor and factory freight.
- Damaged beach entry grating replacement was proposed at time of previous renovation but not added to the project. Upon further inspections and discussion between contractor and customer it has been determined the grates likely damaged by freeze, have become brittle and require replacement.
- **Grating Supplies & Labor - \$9725.00**

Chemical Controller

- CAT 2000 ProPack Chemical Controller
- Controller / Probes / Rotary Flow Switch / Flow Cell / Mounted on PVC Backboard
- Manufacturers Warranty 1 year Parts/5 Year Electronics
- Install and program controller

- **Parts/Factory Freight - \$2,320.89**

- **Project Management/Mobilization/Tech Support/Install - \$1950.00**

PROJECT COMMENTS

- Any unknown repairs required and deemed necessary upon inspection will be addressed with customer and quote submitted for approval, prior to being completed.

Submitted By: Doug Dean

Date: 4-5-2022

Accepted By: _____ **PO#:** _____

Authorized Signature: _____ **Date:** _____

Printed Name: _____